

Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

**ame of Work: Improvements and Development of Santha Sevalal Park in Attur ward no -03
of Yelahanka satellite town sub division**

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. (V-I.No 1.4, Page No-5 of PWD SR 2021-22)								
Santha Sevalal Park								
For SSM foundation (249m fencing + 7m gate)	1	256.00	0.90	0.90	207.36			
					207.36	Cum	204.60	42425.86
Basic Rate Rs. =	186.00							
Add 10% A.W Rs. =	18.60							
Total Rate Rs. =	204.60							
Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)								
Santha Sevalal Park								
For SSM foundation (249m fencing + 7m gate)	1	256.00	0.80	0.15	30.72			
					30.72	Cum	6327.20	194371.58
Basic Rate Rs. =	5752.00							
Add 10% A.W Rs. =	575.20							
Total Rate Rs. =	6327.20							
Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) (V-II, No-5.4, P.No-9 of PWD SR 2021-22)								
Santha Sevalal Park								
For SSM foundation (249m fencing + 7m gate)	1	256.00	0.75	0.60	115.20			
For SSM foundation (249m fencing)	1	249.00	0.60	0.60	89.64			
					204.84	Cum	5964.20	1221706.73
Basic Rate Rs. =	5422.00							
Add 10% A.W Rs. =	542.20							
Total Rate Rs. =	5964.20							

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates (V-I, No-2.4.1, P.No-17 of PWD SR 2021-22).								
Santha Sevalal Park								
For SSM foundation (249m fencing + 7m gate)	1	256.00	0.60	0.075	11.52			
					11.52	Cum	6705.60	77248.51
Basic Rate Rs.=	6096.00							
Add 10% A.W Rs. =	609.60							
Total Rate Rs. =	6705.60							
Fabricating, providing and erecting in position of MS Hot Dip Galvanised Sq. Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery and incidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work. (Data Rate)								
Santha Sevalal Park								
For SSM foundation (249m fencing)	1	249.00		1.80	448.20			
					448.20	Sqm	15630.00	7005366.00
Data Rate	15630.00							
Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineer-in-charge of the work. (Data Rate)								
Santha Sevalal Park								

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
For Gate, 7m width (3.5*2nos)	2	3.50		2.40	16.80			
					16.80	Sqm	21350.00	358680.00
Data Rate	21350.00							
Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3) (V-III Page No.3, Item No.1.1 Cof PWD SR 2021-22)								
Basic rate	74.00							
Area Weightage 10%	7.40							
Total	81.40							
Qty frm Item No-1					207.36	Cum	81.40	16,879.10
Cost of Haulage Excluding Loading and Unloading Taking output 25 t load and lead 10 km = 250 t.km (V-III Page No.3, Item No.1.4 of PWD SR 2021-22) Lead 8 Km								
Basic rate	5.00							
8Km Lead 5*8	40.00							
Area Weightage 10%	4.00							
Total	44.00							
Qty frm Item No-1		207.36	1.28		265.42			
					265.42	t.Km	44.00	11,678.52
Total Construction Cost								8928356.30
12% GST Charges								1071402.76
Sub Total								9999759.05
Utility Shifting, Miscellaneous, Rounding off								240.95
GRAND TOTAL								10000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR, Bangalore circle for year 2021-2022, issue rates and Data Rates.

Assistant Engineer
Ward 03
BBMP Bangalore

Asst. Executive Engineer
Satellite Town Sub Division
BBMP Bangalore

Executive Engineer,
Yelahanka Division
BBMP Bangalore

Administrative Sanction for Rs. ... 100.00 Lakhs

Reques One crane Only

is accorded under head ... P-2178

Deputy Mayor's Sanction

Registered as CE No. ... 10 Subject

to con ... contained in enclosed memo

No BBMP/EE/YNK-01/AS/10/22-23 Dt. 12/5/22

Executive Engineer

Technical Sanction
Accorded For 100.00 Lakhs.
Head of A/C... P-2178
CER NO ... 06 Dt. 12/5/2022

TA

pragana